


Project: PuppetLink//Templestade
Venue: Various
Date: Variuos
Plot: Min Space 1:75 A4 chris.cuthbert@acquismedia.com
 0800 043 0801

Timing:

Please ensure all facilities are pre-rigged in advance of company arrival

Company will arrive 5 hours before doors

Show running time is 1 hour with no interval

Get-out will take 1.5 hours

Dressing rooms:

Please provide 2 clean dressing rooms, with iron & board.

Refreshments are always appreciated!

Staging:

Please ensure staging is a least +750mm above lowest auditorium position

Please provide all scaff & wind-up support to create 9m x 5.4m screen & masking

We would suggest Zenith 5.4m stands & bi or triline.

Screen is lowered from stage at end of piece, please ensure this is possible

Please provide treads where necessary to access thrust & backstage area

Full venue blackout is essential

Sound:

Full Range PA with capacity to serve entire auditorium required

2 x monitors required on stage with seperate mixes controlled from FoH

16 tie lines required from stage to FoH control

Good quality mixing desk & effects unit required at FoH control

Comms required from FoH control to DSL

Lighting:

2 x colour washes of screen required: R74 & L201. Focus to include thrust

Manual control of above required from FoH Sound position